

PLANTING SPECIFICATION

PREPARATION

1. Soil to be graded to smooth, flowing contours to tie into existing levels.

2. Areas within the canopy of existing trees to be re-graded to original levels. These should be worked by hand.

3. Soils shall only be worked when the ground conditions are reasonably dry.

4. Immediately before spreading and regrading topsoil, all stones larger than 75mm in anyone direction shall be removed off site. Likewise, all arisings, contaminants and debris to be removed off site.

TOPSOILING

5. Any imported topsoil shall be free of fragments of roots, aggressive weeds, sticks, straw, subsoil, pieces of bark, concrete, glass, wire, lumps of clay or vegetation, and the like.

6. Topsoil (imported or existing) shall be to a depth of 350mm for all planted areas & 150mm for all grassed areas.

7. Once spread, topsoil to be gently firmed but not compacted.

8. Finished levels shall marry into adjoining areas.

9. All stones and clods of earth greater then 50mm in any one direction shall be removed off site.

SEEDING

10. All grass areas to be seeded with Emorsgate EG22 seed mix sown at supplier's recommended rates.

PIT PREPARATION

11. Heavy Standard tree pits to be 600x600x1000mm
Standard tree pits 500x500x600mm
Transplant pits to be 300x300x300mm
Hedgerows trenches to be 300xlengthx300mm

TREE PLANTING

12. All trees are to be staked and secured as follows: -

i) All Heavy standard (HS) and standard (S) trees are to be double staked to 750mm above ground and secured using a single rubber tie and spacer.

13. One number 80 litre bag of tree planting compost (non peat based) is to be incorporated into the tree pits. Compost must be thoroughly mixed with with excavated (or imported) topsoil.

14. All trees planted in grass are to have a 1m diameter clear zone to the base and are to be mulched to a depth of 50mm with approved medium grade tree bark.

15. All trees to have a spiral rabbit guard fitted immediately upon planting.

PLANTING - SHRUBS

16. Plant handling at the nursery, and during transit up to delivery, shall be in accordance with 'Plant Handling' the booklet published by the Committee for Plant Supply and Establishment (CPSE). The contractor shall comply with clauses 3 & 4 of the above booklet (obtained from the Horticulture Trades Association) which refers to the receipt, unloading and temporary storage of plants.

17. Plants shall be first class examples of their species or variety, free from all pests and diseases with good fibrous root systems and materially undamaged. (Refer to relevant sections of BS3936 Parts 1-4 'Specification of Nursery Stock')

18. All planting is to be in general compliance with BS4428: 1989 'Code of Practice for general landscape operations (excluding hard surfaces)'. Plants shall be planted in groups of 3-15no.

19. The contractor must ascertain for themself the exact location of any under-ground services and maintenance points.

20. Water as necessary to ensure the establishment and continued thriving of planted and grassed matter.

21. Carry out all work when soil and weather conditions are suitable:
i) Do not plant during periods of frost or strong winds.
Plant only during the following periods: -

- Bare root deciduous trees and shrubs:
Late October to late March
- Container grown plants: At any time if ground water and weather conditions are favourable.

22. Planting to be in groups of 3-7no. per species.

23. Ensure that adequate weed control is available.

24. Following planting all Planted Beds and Hedgerows to be mulched to a consolidated depth of 50mm using an approved medium grade tree bark.

25. Following planting all hedgerow trees to have spiral rabbit guards fitted.

PLANTING SCHEDULES

	HEDGEROW PLANTING			
	5 per lin m (double staggered row)			
%	Species	Size	Type	No.
10	Corylus avellana	45-60cm	bare root	137
45	Crataegus monogyna	45-60cm	bare root	630
10	Ilex aquifolium	45-60cm	2L	129
10	Ligustrum vulgare	45-60cm	bare root	137
20	Prunus spinosa	45-60cm	bare root	274
5	Rosa canina	45-60cm	bare root	68
			Total	1375

TREE PLANTING			
Species	Size	Type	No.
Acer campestre (Ac)	10-12cm girth	Rootballed	4
Acer psudoplatanus 'Brilliantissima' (ApB)	12-14cm girth	Rootballed	1
Betula pendula (Bpen)	10-12cm girth	Rootballed	3
Malus tschonoskii (Mt)	10-12cm girth	Rootballed	2
Prunus padus (Pp)	10-12cm girth	Rootballed	1
Prunus x Sargentii (Ps)	12-14cm girth	Rootballed	5
Quercus robur (Qr)	10-12cm girth	Rootballed	3
Sorbus aucuparia (Sa)	10-12cm girth	Rootballed	4
Sorbus aucuparia 'Sheerwater Seedling' (Ss)	12-14cm girth	Rootballed	3
Sorbus aria 'Lutescens' (SaL)	12-14cm girth	Rootballed	7
		Total	26

Tree and Shrub Mix 1 (TSM1)		Bed Name	G	M	Q	Total
0.7m centres		Bed Area (m2	12	22	14	
Species	Size	Type	No.	No.	No.	No.
Acer campestre	40-60cm	bare root	1	3	1	5
Betula pendula	40-60cm	bare root	3	5	3	11
Corylus avellana	40-60cm	bare root	1	3	3	7
Cornus stolonifera	40-60cm	bare root	3	5	3	11
Crataegus monogyna	40-60cm	bare root	6	10	6	22
Prunus spinosa	40-60cm	bare root	3	5	3	11
Prunus padus	40-60cm	bare root	1	3	3	7
Rosa canina	40-60cm	bare root	3	5	3	11
Viburnum opulus	40-60cm	bare root	3	5	3	11
		Total	24	44	28	96

Tree and Shrub Mix 2 (TSM2)		Bed Name	C
0.7m centres		Bed Area (m2	13
Species	Size	Type	No.
Acer campestre	40-60cm	bare root	3
Betula pendula	40-60cm	bare root	1
Corylus avellana	40-60cm	bare root	3
Crataegus monogyna	40-60cm	bare root	5
Cytisus scoparius	40-60cm	bare root	5
Prunus spinosa	40-60cm	bare root	3
Ribes sanguineum	40-60cm	2L	3
Rosa pimpinellifolia	40-60cm	bare root	3
		Total	26

Shrub Mix 1 (SM1)		Bed Name	F	H	K	P	Total
0.7m centres		Bed Area (m2)	10	6	9	15	193
Species	Size	Type	No.	No.	No.	No.	No.
Cornus alba 'Elegantissima'	60-90cm	bare root	3	6	3	5	17
Cornus stolonifera	60-90cm	bare root	3			5	8
Crataegus monogyna	60-90cm	bare root			3	5	8
Cornus canadensis	20-30cm	bare root				3	3
Corylus avellana	40-60cm	bare root			3	3	6
Cytisus scoparius	20-30cm	bare root	3		3	3	9
Hedera helix	20-30cm	1L		6			6
Euonymus europaeus	40-60cm	2L	3		3	3	9
Prunus spinosa	40-60cm	bare root	3			3	6
Rosa pimpinellifolia	40-60cm	bare root	3		3		6
Viburnum opulus	40-60cm	bare root	3				3
		Total	21	12	18	30	81

Suggested shrub species for Ornamental Areas			
Species	Size (cm)	Type	Density per m2
Artemesia 'Powis Castle'	30-40 cm	3L	4
Asplenium scolopendium	45-60 cm	1L	4
Aucuba japonica 'Crotonifolia'	45-60 cm	5L	1.25
Calamgrostis x acutiflora	30-40 cm	2L	4
Carex buchananii	30-40 cm	2L	4
Choisya 'Aztec Peral'	45-60 cm	5L	2
Cistus x corbaniensis	45-60 cm	5L	3
Cotinus 'Flame'	45-60 cm	3L	1.25
Cotoneaster 'Skogholm Coral Beauty	30-40 cm	3L	5
Cytisus x kewensis	45-60 cm	3L	4
Elaeagnus pungens 'Macculata'	45-60 cm	5L	1.25
Escallonia iyeyii	45-60 cm	3L	2
Euonymus 'Silver Queen'	30-40 cm	3L	5
Fuchsia 'Mrs Popple'	30-40 cm	3L	2
Genista lydia	45-60 cm	3L	3
Lavandula stoechas	45-60 cm	3L	4
Lonicera nitida 'Maygreen'	45-60 cm	1L	3
Mahonia x media 'Charity'	45-60 cm	5L	2
Pennisetum alopecuroides 'Hameln'	30-40 cm	3L	2
Phormium tenax 'Yellow Wave'	45-60 cm	2L	specimen
Pieris 'Forest Flame'	45-60 cm	2L	2
Prunus 'Zabeliana'	45-60 cm	3L	2
Skimmia 'Rubella'	45-60 cm	5L	2
Spirea 'Firelight'	45-60 cm	5L	2
Viburnum opulus 'Sterile'	45-60 cm	3L	1.25

Shrub Mix 2 (SM2)		Bed Name	B	D	L	N	R	Total
0.7m centres		Bed Area (m2)	11	9	7	6	5	
Species	Size	Type	No.	No.	No.	No.	No.	No.
Hedera helix 'Glacier'	20-30cm	1L	6	4				10
Rosa canina	30-40cm	bare root	10	8				18
Rubus 'Betty Ashburner'	20-30cm	1L	6	6	14	12	10	48
		Total	22	18	14	12	10	76

Shrub Mix3 (SM3)		Bed	A	E	J	Total
0.7m centres		Bed Area (m2)	7	11	12	
Species	Size	Type	No.	No.	No.	No.
Cotoneaster 'Skogholm Coral Beauty'	30-40 cm	2L		6	6	12
Cytisus praecox	30-40 cm	2L	5	6	6	17
Rosa pimpinellifolia 'Dunwich Rose'	30-40 cm	bare root	5	6	6	17
Prunus 'Zabelliana'	45-60 cm	3L	6	6	6	18
		Total	16	24	24	64

REV A	Removal of ownership boundary	April 2021 VS
REV B	Amends to entrance details and tactile surfacing	June 2021 VS

Lakeside School, Liverpool — **Witherslack Group**

Proposed Landscape Works

General Arrangement Plan

PR/210304/GA/01 REV B

Contractors are advised to check dimensions with the architect before setting out on site

The plant room
Vanessa Swift Bsc Dip LA CMLI
Landscape Architect
M: 07918 081407
F: 08717 145212
E:vanessa@theplantroom.co.uk
www.theplantroom.co.uk
Chartered Member of the Landscape Institute

March 2021

1:200 @ A0
1:400 @ A2