







elevation D




elevation E




existing
elevation D




existing
elevation E




elevation F



elevation G




existing
elevation F



existing
elevation G

proposed floor detail



PLANNING NOTES:-

- 1 Existing stonework to be professionally cleaned.
- 2 New conservation style roof tiles.
- 3 Stone banding course and coping stone to match existing stonework.
- 4 New grey annodised aluminium windows.
- 5 Existing brickwork to be retained and repointed.
- 6 New Rend through colour render finish.
- 7 New garage door to be installed.
- 8 Pikes to receive lead facing.
- 9 Lantern roof lite set over new fibreglass roof covering.
- 10 New grey annodised aluminium bi-folding doors.
- 11 Existing roof coverings are to be retained and refurbished.
- 12 Where slates require replacing a like for like type and style is to be sourced.
- 13 Blank stone window to be re-introduced with glazed panes.
- 14 New slate roof covering to match existing.
- 15 New red sandstone facade to match existing stone.

SERVICES

SERVICES
NO FLUE / SERVICE EXIT LOCATIONS ARE TO BE LOCATED IN THE PRINCIPAL ELEVATIONS. ALL
EXISTING LEADED ROOF VENTS TO MAIN BLOCK AND LOWER LEVELS ARE TO BE RETAINED /
REFURBISHED WHERE NECESSARY.

VENTILATION
WE ARE PROPOSING A WHOLE HOUSE VENTILATION SYSTEM TO BE INTRODUCED INTO THE
SCHEME. ANY OUTLETS WILL BE LOCATED ON REAR ROOF ELEVATIONS.

WINDOWS
ALL EXISTING LEAD LIGHT WINDOWS ARE TO BE RETAINED AND REPAIRED IT IS OUR INTENTION
TO PROVIDE SECONDARY GLAZING TO ALL ELEMENTS THAT REQUIRE THIS PROCEDURE.

Client	Mr. Brendan Carr / Willow Group	Rev	1	Date	June 2024
Job Ref	Milbrook Manor, Keshalee, Village	Drawn	DB		
Drawing Title	Existing elevations				
Job No.	11100				
Scale	1:100				
Date	June 2024				