

- Legend**
- Proposed scrape max depth 600mm
 - Proposed mound using scrape attings to max height 600mm
 - Existing fencing to be maintained
 - Relocated palisade fencing
 - Existing gates
 - Relocated maintenance access gate
 - Existing site levels

Note:
Existing Palisade fence will need to be repaired / component parts replaced on the fence due to vandalism



Project Name
**Halewood Community Learning Centre
Greengates Pitch Construction**

Project Address
**Leather's Lane
Halewood, Knowsley**

Drawing Description
Landscape Proposals

Drawn By J Towers
Date May 2013
Scale 1:500 @ A1

Checked By MKP
Date 15/05/13
Verified By RT
Date 15/05/13

Project Reference Number
1049630

Drawing Number
L32

Revision



Note:
The Soakaway is to be installed below the Land drain which is to be below the scrape

Existing bowtop fencing to be replaced by relocated palisade fencing

Existing pitch to be protected during works and some basic maintenance completed

Existing area of senior pitch size 90 x 50 with 5m over run behind gate and 5m over run on the sides

Existing fencing to be maintained

Proposed relocation of Maintenance Access Gate

Senior Pitch sizes 90 x 50 with 5m over run on the sides and 5m over run between the pitches

No works to be undertaken within the hatched area

Existing access gate

Existing fencing to be maintained

