



CU UNIT REF	ASSOCIATED CU	WEIGHT	DIMENSION	SOUND POWER (COOLING)
RZAG 35A	CU No 5 - 7	52 KG	734mm (H) 872mm (W) 373mm (D)	48 dBA
PUHZ-P	CU No 2 & 4	EXISTING	EXISTING	EXISTING
RZASG 100M	CU No 1	70 KG	990mm (H) 940mm (W) 320mm (D)	70 dBA
RXYSCQ 5T	CU No 3	89 KG	823mm (H) 940mm (W) 460mm (D)	69 dBA

A/C UNIT REFERENCE	ASSOCIATED CONDENSER	UNIT TYPE	LOCATION	FAN COIL DUTY (kW) (Watt)
AC 1a & b FCAG 50B	CU 1 RZASG 100M	Heat Pump Inverter Cassette Mounted Twin Split System (R32)	GROUND FLOOR RETAIL AREA	COOL 4.89 HEAT 6.00
AC 2 PLA-RP	CU 2 PUHZ-P	Heat Pump Inverter Cassette Mounted Split System (Existing)	GROUND FLOOR RETAIL AREA	COOL HEAT
AC 3 FXAQ 20A	CU 3 RKYSCQST	Heat Pump Inverter Wall Mounted Type VRV System (R410A)	GROUND FLOOR CONSULT ROOM 1	COOL 1.80 HEAT 2.50
AC 4 FXAQ 20A		Heat Pump Inverter Wall Mounted Type VRV System (R410A)	GROUND FLOOR CONSULT ROOM 2	COOL 1.80 HEAT 2.50
AC 5 FXAQ 20A		Heat Pump Inverter Wall Mounted Type VRV System (R410A)	GROUND FLOOR CONSULT ROOM 3	COOL 1.80 HEAT 2.50
AC 6 FXAQ 20A		Heat Pump Inverter Wall Mounted Type VRV System (R410A)	GROUND FLOOR HC ROOM 4	COOL 1.80 HEAT 2.50
AC 7 FXAQ 20A		Heat Pump Inverter Wall Mounted Type VRV System (R410A)	FIRST FLOOR CONSULT ROOM 5	COOL 1.80 HEAT 2.50
AC 8 FXAQ 20A		Heat Pump Inverter Wall Mounted Type VRV System (R410A)	FIRST FLOOR CONSULT ROOM 6	COOL 1.80 HEAT 2.50
AC 9 FXAQ 20A		Heat Pump Inverter Wall Mounted Type VRV System (R410A)	FIRST FLOOR CONSULT ROOM 7	COOL 1.80 HEAT 2.50
AC 10 PLA-RP	CU 4 PUHZ-P	Heat Pump Inverter Cassette Mounted Split System (Existing)	FIRST FLOOR RETAIL AREA	COOL HEAT
AC 11 FTXM 35R	CU 5 RZASG 35A	Heat Pump Inverter Wall Mounted Type Split System (R32)	FIRST FLOOR OFFICE	COOL 3.42 HEAT 4.00
AC 12 FTXM 35R	CU 6 RZASG 35A	Heat Pump Inverter Wall Mounted Type Split System (R32)	FIRST FLOOR STAFF ROOM	COOL 3.42 HEAT 4.00
AC 13 FTXM 35R	CU 7 RZASG 35A	Heat Pump Inverter Wall Mounted Type Split System (R32)	FIRST FLOOR CALL CENTRE	COOL 3.42 HEAT 4.00

A/C UNIT REF	POWER SUPPLY	No REQUIRED	ISOLATION	CURRENT (A)	
				START	RUN
RZASG 35A	CONDENSING UNIT 240/150 @16A	3	WEATHERPROOF ROTARY ISOLATOR	N/A	14.53
PUHZ-P	CONDENSING UNIT (EXISTING SUPPLY)	2	WEATHERPROOF ROTARY ISOLATOR	N/A	N/A
RZASG 100M	CONDENSING UNIT 240/150 @32A	1	WEATHERPROOF ROTARY ISOLATOR	N/A	21.50
RXYSCQST	CONDENSING UNIT 240/150 @32A	1	WEATHERPROOF ROTARY ISOLATOR	N/A	19.00
VENT FAN	INLINE FAN 240/150 @5A	4	SWITCH FUSE SPUR	N/A	0.90
AC 3 - 9	INTERNAL AC UNIT 240/150 @5A	7	SWITCH FUSE SPUR	N/A	0.80
HC DAMPER	INTERNAL SPUR 240/150 @5A	1	SWITCH FUSE SPUR	N/A	2.50