





KIRKBY VALLEY
GOLF CLUB

**Kirkby Valley Golf Course
MATERIALS SCHEDULE
Planning Application
Rev. D**

Kirkby Valley Golf Course Paving Schedule

CODE	NAME	SAMPLE REQUIRED	PRODUCT MATERIAL	PRODUCT CODE / COLOUR	FINISH /EDGING	IMAGE
	Cart Path	on site from contractor	Concrete	natural concrete finish	pencil edge	
	Access Road	on site from contractor	Tarmac	To match existing road	pre cast concrete heel kerb edge	
	Clubhouse Terrace	Yes	Larissa Granite	Natural (beige)	Fine Picked	
	Car Parking 1 (near Driving Range)	Yes	Marshalls Piora Permeable Block Paving	Bracken	pre cast concrete heel kerb edge	
	Car Parking 2 (near Clubhouse)	Yes	Marshalls Piora Permeable Block Paving	Buff	pre cast concrete heel kerb edge	
	Road Crossings	Yes	Marshalls Piora Permeable Block Paving	Brindle	-	
	Footpath 1	Yes	SureSet Resin Bound Gravel	Norwegian Bronze	pre cast concrete flush kerb edge	
	Footpath 2	Yes	SureSet Resin Bound Gravel	Norwegian Pearl	pre cast concrete flush kerb edge	
	Access Footpath	on site from contractor	Tarmac	To match existing path	pre cast concrete flush kerb edge	
	Clubhouse Paving 1	Yes	Marshalls Piora Flag Paving	Natural	-	
	Clubhouse Paving 2	Yes	Marshalls Piora Flag Paving	Charcoal	-	
	Tactile Paving	Yes	Marshalls Blister Paving	Natural	-	

	Concrete Yard	on site from contractor	concrete	natural concrete finish	pre cast concrete	
	Wooden Terrace	Yes	Millboard Wood Composite Decking: Enhanced Grain	Coppered Oak	-	
	Artificial Grass Type 1 (for Greens)	Yes	Artificial Grass	-	-	
	Artificial Grass Type 2 (for Fairways)	Yes	Artificial Grass	-	-	



Kirkby Valley Golf Course Surface Finishes Schedule

CODE	NAME	SAMPLE REQUIRED	DESCRIPTION / MATERIAL	FINSIH / MOUNTING	COLOUR	SIZE	IMAGE
	Sand	YES	bunker sand, sub angular	Natural	Natural	0.25-1.25 mm Grade	
	Boulders	YES	Adventure golf boulders; size approx: 1=1000 x 1500 x 1000mm ht 2=800 x 1500 x 450mm ht 3=500 x 500 x 1000mm ht 4=200 x 500 x 700mm ht	Smooth Natural	Varies	Varies	

Kirkby Valley Golf Course Edges Schedule

CODE	NAME	SAMPLE REQUIRED	Location	DESCRIPTION / MATERIAL	FINISH	COLOUR	SIZE (D, L, W)	IMAGE
	Upstand Kerb	on site from contractor	Roadside (As Per Design)	Pre Cast Concrete	Standard	Grey	150x915x150mm Precast Kerb	
	Flush kerb	on site from contractor	Block and Flag Paving Edge (As Per Design)	FLUSH KERB or HEEL KERB	Light grey	Grey	600 x 150 x 50	
	Aluminum edge	on site from contractor	Resin Bound Gravel Edge (As Per Design)	Aluminum Edge Kinley AluExcel Flexible	-	Stainless Steel Effect	To Engineer's details/approval	


Kirkby Valley Golf Course Fixtures Schedule

NAME	SAMPLE REQUIRED	SUPPLIER CODE	SUPPLIER DETAILS	DESCRIPTION / MATERIAL	COLOUR	LOCATION	IMAGE
BENCH	YES	ESCOFET PRIMA MARINA	Marshalls or similar approved	UHPC Concrete with Teakwood Cladding on the Top Surface	Acid-Etched and Waterproofed/ Fixing Anchored with Screws	Site-Wide	
LITTER BIN	YES	-	Marshalls or similar approved	Refer to details	Refer to details	Site-Wide	
CYCLE STAND	YES	Omega HOM 694	Furnitubes or similar approved	Stainless steel	Satin polished; Root fixed	Site-Wide	
PRIMARY DIRECTION SIGN	NO	-	Bespoke	See drawing G935 221 Wayfinding Signage	See drawing G935 221 Wayfinding Signage	Site-Wide	
SECONDARY DIRECTION SIGN	NO	-	Bespoke	See drawing G935 221 Wayfinding Signage	See drawing G935 221 Wayfinding Signage	Site-Wide	
PLANTER	NO	-	Bespoke	Brick wall rendered	White	Site-Wide	

Kirkby Valley Golf Course Fencing Schedule

CODE	NAME	DESCRIPTION / MATERIAL	FINISH	COLOUR	SIZE mm (WxH)	LOCATION	IMAGE
	Driving Range Ball Stop Fence	ball stop fencing in black	black painted stanchions, black nylon ball stop netting	black	15m heigh at 7m spacing	encapsulating the driving range outfield	
	Entrance Fence	Steel Fence	Powder Coated	Black	2.0m high	Around Entrance Area	
	Entrance Gate	Steel Gate	Powder Coated	Black	2.0m high	Around Entrance Area	
	Entrance Sliding Gate	Track mounted Steel Sliding Gate	Powder Coated	Black	2.0m high	Around Entrance Area	
	Adventure Golf Fence	Steel bow top fence	Powder Coated	Black	1.2m high	to perimeter of the Adventure golf area	
	Maintenance Areas Fence	Welded V crimped Mesh Panel. To BS1722-14 category 1. Finished in PVCr Coating	galvanised steel with green PVC coating	Green	2.4m height, 2.75m between posts	Around Maintenance Yard	
	Maintenance Areas Gate	Welded V crimped Mesh Panel. To BS1722-14 category 1. Finished in PVCr Coating	galvanised steel with green PVC coating	Green	2.4m height	Around Maintenance Yard	

Kirkby Valley Golf Course Lighting Schedule

CODE	NAME	SAMPLE REQUIRED	SUPPLIER DETAILS	DESCRIPTION / MATERIAL	FINISH	COLOUR	SIZE	LOCATION	IMAGE
	STREET LIGHT	contractor to supply	Street Light	contractor to supply	galvanised Steel with LED luminare	grey	4m	roads and parking	
	POLE LIGHT	contractor to supply	DW WINDSOR SILKA-MAX	contractor to supply	Stainless Steel	Robust and corrosion resistant	2.5m	Site Wide Park Lights	
	BOLLARD LIGHT	contractor to supply	ZENITH ZEN901 BS304 9LED	Furnitubes T: +44 (0)20 8378 3200 sales@furnitubes.com or Equal Approved	Stainless Steel	Satin Polished/ Ground Mounted	1.1m	Site-Wide	
	UPLIGHTERS	contractor to supply	BA40	contractor to supply	Aluminium	Acrylic liquid paint	Grey	Site Wide Tree Uplighters	
	BERM LIGHTING	contractor to supply	Abacus Lighting or similar approved	150 w SONP-T Orsam Flood Light	as manufacter supplied	as manufacter supplied	as manufacter supplied	12 locations to driving range outfield	

Kirkby Valley Golf Course Paint Colours Schedule

CODE	NAME	LOCATION	DESCRIPTION / MATERIAL	COLOUR
	Painted Gates and Fences/Railings/Posts		Gloss Emulsion	RAL 3007 (Black)
	Wood Stain		to all Cedar Cladding Areas	Natural
	Painted Render		Maintenance building	RAL 9016 (White)

Kirkby Valley Golf Course Building Materials Schedule

CODE	NAME	SUPPLIER DETAILS	DESCRIPTION / MATERIAL	FINSIH	COLOUR	LOCATION	IMAGE
	Cedar Cladding	contractor to confirm	white cedar cladding	clear stain	natural	cladding to maintenance building and driving range bays	
	Slate Roof	contractor to confirm	--	--	--	slate roofing to pitched roofs on driving range building	
	Grey Gloss Powder Coat	contractor to confirm	profiled metal roof	pvc coating to profiled metal	dark grey	maintenance central building	
	Roller Shutters	contractor to confirm	galvanised roller shutter	pvc coating	dark green	maintnenance central building and driving range	
	Driving range zinc cladding	contractor to confirm	standing seam zinc	weathered coating	grey	driving range	
	Glazing and doors to driving range	contractor to confirm	framless glazing with automatic sliding doors inset	self cleaing glazing with manifestations	anthracite grey door frames	driving range buiding	
	Maintenance building doors and windows	contractor to confirm	composite doors and windows	matt	anthracite grey	maintenance central building	
	Maintenance building roofing	contractor to confirm	roof	matt	grey	maintenance central building	