NORTH

2.4x43m VISIBILITY SPLAY

61.0m

Und

STONEY LANE

Material Change

7 Lin m H3

548 m² WFM1

98 Lin m MNH

599 m² NWP

10 Lin m H3

11 Lin m H3

116 m² NWP

223 m² WFM1

6 Lin m H3

17 Lin m H3

91 Lin m MNH

12 Lin m H1

10 Lin m H1

15 Lin m H1

6 Lin m H1

7 Lin m H1

11 Lin m H1

16 Lin m H1

325 m² FLM1

48 Lin m H

14

27

29

138

189

190

191

192

193

194

195

196

197

198

199

200

201

202

203

204

205

156

155

154

153

152

151

150

149

148

147

146

145

144

143

142

141

140

123

124

125

126

188

EMA35 TETFORD OPP

EMB3 I HARRETON AS

EMA42 BITTESFORD AS

EMG42 CORKHAM AS

EMA32 BRAMBLEFORD OPP AS

EMA22 BEAFORD OPP AS

EMA33 EYNSFORD AS

EMA44 HENFORD OPP AS

EMA22 BEAFORD AS

EMA32 BRAMBLEFORD AS OPP

EMB3 I HARRETON AS

EMA35 TETFORD OPP

EMA44 HENFORD AS

EMA35 TETFORD OPP

EMA35 TETFORD EMA35 TETFORD OPP

EMA22 BEAFORD EMA22 BEAFORD OPP AS

EMA33 EYNSFORD EMA22 BEAFORD EMA33 EYNSFORD AS AS AS

EMA35 TETFORD EMA35 TETFORD OPP

Ac Bp Cb Qr Sa Ps Pa Tc Pe Pø Bf Pu Pc Pd Sj Si Ag Pa

KEY

Proposed Trees in POS
See plant schedule and specification for details on species, nursery grades

Proposed Trees
See plant schedule and specification for details on species, nursery grades an quantities

Proposed shrub planting
See plant schedule and specification for details on species, nursery grades and quantities

Proposed Hedges - Plots
See plant schedule and specification for details on species, nursery grades and quantities

Proposed Hedgerows - In POS and Managed by Management Company
See plant schedule and specification for details on species, nursery grades and quantities

Proposed Grass to Plots
Amenity Grade Turf 2761 sqm

Proposed Marginal Planting MP1
See plant schedule and specification for details on species, nursery grades and quantities

Proposed Wildflower planting
See plant schedule and specification for details on species, nursery grades and quantities

Proposed Flowering Lawn
See plant schedule and specification for details on species, nursery grades and quantities

Proposed Native Whip Planting
See plant schedule and specification for details on species, nursery grades and quantities

Rev	Date	Description	Initials
P8	11.08.26	Amended to Clients Comments	KLJ
P7	10.08.26	Amended to Clients Comments	KLJ
P6	06.08.26	Updated to reflect revised layout	KLJ
P5	13.03.26	Emphasise POS Hedge Graphics - Adjust Schedule	PGG
P4	16.01.26	Scale bar added	KLJ
P3	09.12.25	Minor Layout and Basin Updates	PGG
P2	04.12.25	Layout and Basin Updates	PGG
P1	19.11.25	Initial Issue for Comment	PGG

Scale 1:200@A1

0 1 2 3 4 5 10 15m

pgla landscape architects

PGLA Ltd
Landscape Architects
Station Hop Offices
815 Stockport Road
Manchester
M19 3BS

t: 0161 238 9138
e: info@pgla.co.uk
w: www.pgla.co.uk

Client
TAYLOR WIMPEY UK LIMITED

Taylor Wimpey

Project
Glen Dimplex_Stoney Lane_Whiston

Description
PLANTING PLAN
SHEET 3

Status
FOR PLANNING

Scale	Drawn	Checked	Date
1:200@A1	PGG	KLJ	NOV 25

Job number	Drawing number	Revision
WHI2508	PP01.03	P8

Original size 100mm @ A1