Street Tree

Abbrev.	Botanical Name	Common Name	Girth/ Dia. cm	Height cm	Root Zone	Specification	Number
A ca 'El'	Acer campestre 'Elsrijk'	Field Maple 'Elsrijk'	18-20	400-450	100-200L	EHS; clear stem min. 200cm	Counted
A lam	Amelanchier lamarckii	Juneberry		300-350	RB	3x; Multi-stem; bushy; 3 stems min.	Counted
B pe - 1	Betula pendula	Common Silver Birch	14-16	400-450	RB	3x; EHS; clear stem 175-200cm; 5 brks	Counted
B pe - 2	Betula pendula	Common Silver Birch		350-400	RB	3x; Multi-stem; bushy; 3 stems min.	Counted
C be - 2	Carpinus betulus	Common Hornbeam	16-18	400-450	80-100L	EHS; clear stem min. 200cm	Counted
P s	Pinus Sylvestris	Scots Pine		300-350	RB	4x; leader with laterals; feathered	Counted

Greenspace

Abbrev.	Botanical Name	Common Name	Girth/ Dia. cm	Height cm	Root Zone	Specification	Number
A lam	Amelanchier lamarckii	Juneberry		300-350	RB	3x; Multi-stem; bushy; 3 stems min.	Counted
B pe - 1	Betula pendula	Common Silver Birch	16-18	400-450	RB	3x; EHS; clear stem min. 200cm	Counted
B pe - 2	Betula pendula	Common Silver Birch		350-400	RB	3x; Multi-stem; bushy; 3 stems min.	Counted
C be - 1	Carpinus betulus	Common Hornbeam	10-12	300-350	B	2x; SS; clear stem 175-200cm; 4 brks	Counted
C be - 2	Carpinus betulus	Common Hornbeam	16-18	400-450	RB	3x; EHS; clear stem min. 200cm	Counted
F s	Fagus sylvatica	Common Beech	14-16	400-450	45-85L	EHS; clear stem 175-200cm; 5 brks	Counted
P s	Pinus Sylvestris	Scots Pine		300-350	RB	4x; leader with laterals; feathered	Counted
Q r - 1	Quercus robur	Common Oak	8-10	250-300	B	2x; Std; clear stem 175-200cm; 3 brks	Counted
Q r - 2	Quercus robur	Common Oak	16-18	400-450	RB	3x; EHS; clear stem min. 200cm	Counted



NOTES:

1. DO NOT SCALE FROM THIS DRAWING. ALWAYS WORK TO NOTED DIMENSIONS.
2. ALL SETTING OUT, LEVELS AND DIMENSIONS TO BE CHECKED ON SITE PRIOR TO THE INSTALLATION OF MATERIALS AND ANY DISCREPANCIES ARE TO BE BROUGHT TO THE ATTENTION OF THE CONTRACT ADMINISTRATOR IMMEDIATELY.
3. THIS DRAWING MUST BE READ WITH THE RELEVANT SPECIFICATION DOCUMENTS AND DETAIL DRAWINGS. ANY DISCREPANCIES MUST BROUGHT TO THE ATTENTION OF THE CONTRACT ADMINISTRATOR IMMEDIATELY.
4. THIS DRAWING IS COPYRIGHT PROTECTED AND MAY NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN AUTHORITY.
5. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE STATED.
6. NOTE DRAWING SUITABILITY CODE SHOWN BELOW. DRAWING NOT TO BE USED FOR CONTRACTUAL AGREEMENT WITHOUT A1 STATUS.

THIS DRAWING WAS PLOTTED ON:

09/12/2025

REVISION HISTORY

DATE	REV	ZONE	DESCRIPTION	CHK
11/11/2025	2		General Update	MC
04/12/2025	3		Added Trees	MC
09/12/2025	4		Scale bar Added	MC

KEY

GENERAL INFORMATION

- APPLICATION SITE BOUNDARY
- POWER LINES

SOFTWORKS

- CLEAR-STEM TREE PLANTING — Refer to Planting Schedule
- MULTI-STEM TREE PLANTING — Refer to Planting Schedule
- 'WOODLAND FRINGE' PLANTING — Refer to Planting Schedule
- SUDs PLANTING — Refer to Planting Schedule
- SCREENING PLANTING — Refer to Planting Schedule
- WILDFLOWER — Refer to Planting Schedule
- HEDGE — Refer to Planting Schedule — Total Lin M. 937.2m

0m 1m 5m 10m 20m 40m

ORIGINATOR

Layer.studio

W layer.studio
T 01625 523 157
E manchester or newcastle@layer.studio

MANCHESTER
8b Grove Street
Wilmslow
Cheshire
SK9 1DR

NEWCASTLE
Studio 29
39 High Bridge Works
Newcastle-upon-Tyne
NE1 1EW

Client
Starship Group

Project
Halsnead Farm
Widnes

Drawing Title
Softworks

Created By	Checked By	Scale	Sheet Size
MC	ST	1:500	A1

Project Number	Originator	Volume	Level	File Type	Discipline	Number
458	LYR	XX	ZZ	DWG	L	3001

Work Stage	Status	Revision
Stage 1	SX Review & comment	4