

Series 8000 Drawings
LPA Site Location Plan
LPA GA Building Plans
LPA GA Elevations

Material Key	
Number	Material name
E2	Area of existing brick barn wall to be removed where primary school abuts barn. The corner to be rebuilt to SE specification.
T1	Existing retained tiles to be reinstated on new battens and underlaid on revised trusses.
T2	Install new proposed external block wall construction and render to match existing. The corner to be rebuilt to SE design and removing existing brick barn wall. Wall type to achieve U-value = 0.18W/m ² K by Main Contractor design and Specification.
T3	Existing wall to be re-rendered to match existing colour.
T5	New Glazed External Single Door with Glazed side Panel to comply with Building Regulations L2B U-value = 1.0W/m ² K by Manufacturer design and Specification.

[illegible]

Project
Witherslack Group - Lakeside School - Ph 2
Naylor's Rd, Liverpool L27 2YA

Primary School Elevations as Proposed

Drawn by	AW	Created	03.21
C4 Job no.	20-034	1 : 100	@ A1
Drg no.			
20034-C4P-B1-ZZ-DR-A-2101.			
Status	Purpose of Issue	Rev	
S2	FOR INFORMATION	P11	