PLANT SCHEDULE

Trees

Abbr	Species	Supply	Height	Girth	Number
ACECAM	Acer campestre	HStd: Clear stem minimum 200cm: BR	350-425cm	12-14cm	8
ACEPLEQ	Acer platanoides 'Emerald Queen'	EHStd: Clear stem minimum 200cm: RB	450-625cm	16-18cm	15
BENI	Betula nigra	HStd: Clear stem minimum 200cm: RB	350-425cm	12-14cm	14
BEPE	Betula pendula	HStd: Clear stem minimum 200cm: RB	350-425cm	12-14cm	18
BETJACA	Betula utilis jacquemontii	HStd: Clear stem minimum 200cm: RB	350-425cm	12-14cm	11
BETJACA	Betula utilis jacquemontii	EHStd: Clear stem minimum 200cm: RB	450-625cm	16-18cm	41
CARBETFF	Carpinus betulus 'Frans Fontaine'	EHStd: Clear stem minimum 200cm: RB	450-625cm	16-18cm	36
FAGPURA	Fagus sylvatica 'Purpurea'	SM: Clear stem minimum 200cm: RB	600cm+	20-25cm	3
FAGPURA	Fagus sylvatica 'Purpurea'	EHStd: Clear stem minimum 200cm: RB	450-625cm	16-18cm	2
LIQSTW	Liquidambar styraciflua 'Worplesdon'	SM: Clear stem minimum 200cm: RB	600cm+	20-25cm	7
MAGGAI	Magnolia 'Galaxy'	HStd: Clear stem minimum 200cm: RB	350-425cm	12-14cm	3
MALEV	Malus 'Evereste'	HStd: Clear stem minimum 200cm: RB	350-425cm	12-14cm	1
MALTRI	Malus triobata	EHStd: Clear stem minimum 200cm: RB	450-625cm	16-18cm	24
MALTS	Malus tschonoskii	EHStd: Clear stem minimum 200cm: RB	450-625cm	16-18cm	14
PRUPLEA	Prunus avium 'Plena'	EHStd: Clear stem minimum 200cm: RB	425-600cm	14-16cm	12
PRUPLEA	Prunus avium 'Plena'	EHStd: Clear stem minimum 200cm: RB	450-625cm	16-18cm	26
PYRCHAC	Pyrus calleryana 'Chanticleer'	EHStd: Clear stem minimum 200cm: RB	450-625cm	16-18cm	48
SORAU	Sorbus aucuparia	HStd: Clear stem minimum 200cm: BR	350-425cm	12-14cm	2
TILCOGR	Tilia cordata 'Green Spire'	EHStd: Clear stem minimum 200cm: RB	450-625cm	16-18cm	3

Total :288

Specimen Shrubs

Abbr	Species	Pot Size	Height	Habit	Number
PHOFRR	Photinia x fraseri 'Red Robin'	70L	225-250cm	Std: 12-14cm girth	26

Total :26

Single Species Hedgerows

Abbr	Species	Pot Size	Height	Habit	Density	Number
ELAEB	Elaeagnus ebbingei	10L	80-100cm	Bushy	0.4Ctr	109
EUJAPJH	Euonymus japonicus 'Jean Hugues'	10L	40-60cm	Bushy	0.4Ctr	248
LAVANVE	Lavandula angustifolia 'Vera'	10L	30-40cm	Bushy	0.35Ctr	445
VIBPRIA	Viburnum tinus 'Eve Price'	10L	40-60cm	Bushy	0.4Ctr	1851

Total :2653

Native Hedgerow Mix

Abbr	Species	Supply	Height	Density	Number
CORAV	Corylus avellana	BR	60-80cm	0.4Ctr Triple Staggered at 0.25m offset	327
CRAMON	Crataegus monogyna	BR	125-150cm	0.4Ctr Triple Staggered at 0.25m offset	1089
ILEAQ	Ilex aquifolium	2L	40-60cm	0.4Ctr Triple Staggered at 0.25m offset	218
PRUSP	Prunus spinosa	BR	60-80cm	0.4Ctr Triple Staggered at 0.25m offset	327
ROSCA	Rosa canina	BR	40-60cm	0.4Ctr Triple Staggered at 0.25m offset	66
VIBOP	Viburnum opulus	BR	40-60cm	0.4Ctr Triple Staggered at 0.25m offset	153

Total :2180

Shrubs

Abbr	Species	Pot Size	Height	Habit	Density	Number
AUCJACR	Aucuba japonica 'Crotonifolia'	10L	40-60cm	Bushy	0.7Ctr	5
AUCVARA	Aucuba japonica 'Variegata'	10L	60-80cm	Bushy	0.7Ctr	96
ELAEBGE	Elaeagnus ebbingei 'Gilt Edge'	10L	60-80cm	Bushy	0.7Ctr	5
FAJA	Fatsia japonica	10L	60-80cm	Bushy	0.7Ctr	96
HEBSU	Hebe 'Sutherlandii'	10L	30-40cm	Bushy	0.7Ctr	20
HYPTRIA	Hypericum moseranum 'Tricolor'	10L	40-60cm	Bushy	0.7Ctr	4
PHOFRRER	Photinia fraseri 'Red Robin'	10L	80-100cm	Bushy	0.7Ctr	101
PITTEVA	Pittosporum tenuifolium 'Variegatum'	10L	40-60cm	Bushy	0.7Ctr	96
PRULAZA	Prunus laurocerasus 'Zabeliana'	10L	40-60cm	Bushy	0.7Ctr	4
VIBPRIA	Viburnum tinus 'Eve Price'	10L	40-60cm	Bushy	0.7Ctr	3

Total :430

Amenity Shrubs - Cornus Mix

Abbr	Species	Pot Size	Height	Habit	Density	Number
CORALS	Cornus alba 'Sibirica'	3L	60-80cm	Branched	0.8Ctr	35
CORSAMF	Cornus sanguinea 'Midwinter Fire'	3L	60-80cm	Branched	0.8Ctr	35
CORSTF	Cornus stolonifera 'Flaviramea'	3L	60-80cm	Branched	0.8Ctr	35

Total :105

Marginal / Aquatics

Abbr	Species	Supply	Density	Number
CALPA	Caltha palustris	Plug 100cc	10/m²	182
EUPCAN	Eupatorium cannabinum	Plug 100cc	10/m²	182
FILUL	Filipendula ulmaria	Plug 100cc	10/m²	207
LYTSA	Lythrum salicaria	Plug 100cc	10/m²	182
MYOSC	Myosotis scorpioides	Plug 100cc	10/m²	182
STAPA	Stachys palustris	Plug 100cc	10/m²	182
VERBECC	Veronica beccabunga	Plug 100cc	10/m²	182

Total :1299

Bulbs

Abbr	Species	Supply	Density	Number
CROCHBP	Crocus chrysanthus 'Blue Pearl'	Bulb	25/m²	664
CROCHCB	Crocus chrysanthus 'Cream Beauty'	Bulb	25/m²	664
GALNI	Galanthus nivalis	Bulb	25/m²	885
MUSARBS	Muscari armeniacum 'Blue Spire'	Bulb	25/m²	885
NARCA	Narcissus 'Canaliculatus'	Bulb	25/m²	664
NARTT	Narcissus 'Tete a Tete'	Bulb	25/m²	664

Total :4426

KEY

Application site boundary.

Existing vegetation to be retained. Refer to approved tree survey for exact details on tree retention and removal.

Existing vegetation to be removed for construction. Refer to approved tree survey for exact details on tree retention and removal.

Drainage easements. Refer to drainage information for details.

Drainage facilities, proposed locations for underground storage tanks. Refer to drainage information for details.

Turf & Seeding

Turf
Turf to gardens to be laid as Rolawn 'Medallion', or similar approved.

Amenity Grassland
EL1 Flowering Lawn Mix, as supplied by Emorsgate Seeds (www.wildseed.co.uk) or similar approved.

Meadow Grassland
EM3 Special General Purpose Meadow Mix, as supplied by Emorsgate Seeds (www.wildseed.co.uk) or similar approved.

Wet Meadow Grassland
EM8, seed mixture for wetlands, as supplied by Emorsgate Seeds (www.wildseed.co.uk) or similar approved.

Street Furniture


Wayfinding signage
Timber fingerpost wayfinding signage to be located throughout the development to include waymarkers for Kirkby Town Centre, Kirkby Leisure Centre & Valley Park. Signage to be supplied by Border Signs & Graphics in neutral colours as set out below, or similar approved.

Drawing to be read in conjunction with GL1859 SP 01A Landscape Specification.



Image showing the type of wayfinding signage

Location Plan



Rev	Date	Notes	Int.
A	01/11/22	Updated to latest layout.	AD
B	05/12/22	Updated to latest layout.	AD
C	07/11/23	Updated to latest layout.	AD
D	07/03/24	Updated to latest layout.	AD
E	28/10/24	Updated to latest layout. Landscape specification notes updated, please refer to drawing GL1859 00.	JW
F	05/03/25	Updated to latest layout.	EW
G	08/03/25	Wayfinding signage added and plant species updated to DWH handbook.	EW
H	15/05/25	Updated to client comments.	EW
J	31/07/25	Landscape adjacent to plot 335 altered.	EW
K	19/08/25	Landscape updated to client comments and latest planning layout.	EW
L	03/09/25	Landscape updated to client comments.	EW
M	09/09/25	Planting adjacent to plot 335 removed.	EW
N	08/01/26	Wetland and Meadow species updated.	EW
O	05/02/26	Drainage information updated and planting adjusted over trans.	EW

Project
Cherryfield Drive, Kirkby

Drawing title
Landscape Proposals - Infrastructure
(Sheet 5 of 5)

Status
PLANNING

Client
David Wilson Homes North West

Scale	Drawn By	Checked By
1:500 @ A0	AD	JW

Date
23/09/2022

Reference
GL1859 05O

golby+luck landscape architects

Landscape Institute Registered Practice

Scale Bar
0m 10m 20m 30m 40m 50m

tel: 01530 265688 | email: info@golbyandluck.co.uk | web: www.golbyandluck.co.uk

This drawing has been produced by GOLBY AND LUCK LTD © all rights reserved. Ordnance Survey Licence No. AC0000816156 registered with ProtonP Office: 207 Leicester Road, Ibstock, Leicestershire, LE67 6HP