

Plant Schedule

QTY	UNIT	CODE	PLANT NAME	STOCK	FORM	GIRTH / HEIGHT
Trees						
5	No.	ACE ELS hs	Acer campestre 'Elsrijk'	RB	STD	12-14cm
5	No.	ALN GLU hs	Alnus glutinosa	RB	STD	12-14cm
4	No.	BET PEN 12	Betula pendula	RB	STD	12-14cm
9	No.	FAG SYL hs	Fagus sylvatica	RB	STD	12-14cm
5	No.	SAL CAP hs	Salix caprea	RB	STD	12-14cm
6	No.	SOR AUC hs	Sorbus aucuparia	RB	STD	12-14cm

QTY	UNIT	CODE	PLANT NAME	STOCK	SIZE
Hedges					
106	m	Fas Hedge	Fagus sylvatica	C10L	40-60cm
424	No.	Plants spaced @4/m in a Double Staggered Row			

PERCENT	QTY	UNIT	PLANT NAME	STOCK	SIZE
Hedge Mixes					
20m NATIVE HEDGE MIX 12 planted @6/m in a Double Staggered Row					
25%	314	No.	Crataegus monogyna	B Trans	60-80cm
20%	251	No.	Ligustrum vulgare	C3L	60-80cm
15%	188	No.	Corylus avellana	B Trans	60-80cm
25%	314	No.	Ilex aquifolium	C3L	40-60cm
15%	188	No.	Viburnum Opulus	B Trans	60-80cm
To be planted in species groups of approximately 3-7.					

PERCENT	QTY	UNIT	PLANT NAME	STOCK	SIZE
Plant Mixes					
159m2 RAIN GARDEN MIX planted @5/m2					
15%	119	No.	Anemone x hybrida Honorine Jobert	C3L	Full pot
10%	80	No.	Carex buchananii	C3L	Full pot
10%	80	No.	Echinacea purpurea	C3L	Full pot
20%	159	No.	Hemerocallis 'Pink Damask'	C2L	Full pot
5%	40	No.	Iris sibirica 'Perry's Blue'	C2L	Full pot
10%	80	No.	Carex stricta	C2L	Full pot
10%	80	No.	Ligularia przewalskii	C2L	Full pot
10%	80	No.	Persicaria amplexicaulis alba	C2L	Full pot
10%	80	No.	Carex siderosticha	C2L	Full pot
4m2 GROUNDCOVER MIX 8 planted @5/m2					
20%	4	No.	Tiarella Grandiflora	C3L	40-60cm
30%	6	No.	Epimedium sulphureum	C2L	20-30cm
10%	2	No.	Vinca minor	C2L	20-30cm
30%	6	No.	Pachysandra terminalis	C2L	20-30cm
10%	2	No.	Ajuga reptans	C2L	20-30cm
Individual varieties to be planted in groups of approximately 10-15.					
123m2 NATIVE SHRUB MIX B planted @2/m2					
15%	369	No.	Cornus sanguinea	B Trans	60-80cm
15%	369	No.	Corylus avellana	B Trans	60-80cm
10%	246	No.	crataegus monogyna	B Trans	60-80cm
10%	246	No.	Prunus spinosa	B Trans	60-80cm
10%	246	No.	Rhamnus frangula	B Trans	60-80cm
10%	246	No.	Salix caprea	B Trans	60-80cm
10%	246	No.	Sambucus nigra	B Trans	60-80cm
10%	246	No.	Viburnum opulus	B Trans	60-80cm
5%	123	No.	Rosa canina	B Trans	40-60cm
5%	123	No.	Ilex aquiofilium	C2L	40-60cm
Individual varieties to be planted in groups of 3-5.					
112m2 ORNAMENTAL SHRUB MIX A planted @3/m2					
20%	67	No.	Potentilla fruticosa 'Goldfinger'	C3L	20-30cm
20%	67	No.	Salix lanata	C3L	20-30cm
20%	67	No.	Skimmia japonica 'Rubella'	C3L	30-40cm
15%	50	No.	Cornus alba 'Kesselringii'	C3L	40-60cm
15%	50	No.	Prunus laurocerasus 'Zabeliana'	C3L	30-40cm
10%	34	No.	Salix purpurea 'Nana'	C3L	40-60cm
553m2 POLLEN AND NECTAR WILDFLOWER MIX planted @1/m2					
100%	553	No.	No. Superior Pollen and Nectar Wildflower Seed Mix	Seed	
Seeded at 2g m2 over prepared ground from Habitat Aid					
1118m2 WET MEADOW MIX planted @1/m2					
100%	1118	No.	No. Wet Wildflower Meadow Seed Mix	Seed	
Seeded at 4g m2 over prepared ground from Habitat Aid					

Notes and Abbreviations

B	=	Bare root (bagged).
C	=	Container (or pot) grown, followed by size of the container (or pot).
FORM	=	Shape of tree as supplied by the nursery.
QTY	=	Quantity
RB	=	Rootballed (balled and wrapped).
SIZE	=	Height or Spread of juvenile plant.
Std	=	(clear stem) Standard.
STOCK	=	Root condition/protection method eg Bare root.
Trans	=	Transplant (or undercut seedling).

- Refer to specification for further information.
- All plants to be completely hardened off
- Substitutions to be agreed with Landscape Architect.

Do not scale this drawing (printed or electronic version).

Contractors must check all dimensions from site

This drawing is copyright and is for use on this site only. This drawing should be read in conjunction with all relevant consultants drawings and specialist subcontractors / supply chain drawings and specifications.

All works to be carried out in accordance with the latest British Standards / Codes of Practice unless specifically directed otherwise in the specification.

Responsibility for the reproduction of this drawing in paper form, or issued in electronic format, lies with the recipient to check that all information has been replicated in full and is correct when compared to the original paper or electronic image.

Graphical representations of equipment on this drawing have been co-ordinated, but are approximations only. Please refer to the specifications and / or details for actual sizes and / or specific contractor construction information.

Notes:-

KEY

- **Site Red Line Boundary**

Soft Works

- **Existing Trees Retained**
- **Existing Trees Removed**
- **Proposed Tree Planting** Clear stem heavy standard tree.
- **Proposed Hedge Planting**
- **Proposed Native Hedge Planting** Mixes species native shrubs
- **Proposed Groundcover Planting**
- **Proposed Ornamental Shrub Planting** Ornamental shrub mix.
- **Proposed Native Shrub Planting** Native shrub mix.
- **Proposed Turf Grass** To front gardens.
- **Proposed Seeded Amenity Grass**
- **Proposed Seeded Species Rich Wildflower Meadow**
- **Proposed Wet Meadow** Seed mix. To pond area.
- **Existing Vegetation** To be retained and enhanced.
- **Proposed Rain Gardens** Planting mix.

REV.	DATE	DESCRIPTION	DRAWN	CHK'D
P04	21/03/25	FOURTH ISSUED	TH	SA
P03	28/02/25	THIRD ISSUED	RS	SA
P02	06/02/25	SECOND ISSUED	SW	SA
P01	20/01/25	FIRST ISSUED	TH	SW

URBAN GREEN

A: Ground Floor, The Tower, Deva City Office Park, Trinity Way, Manchester M3 7BF

T: +44 (0) 161 312 3131

weareurbangreen.co.uk

Client: MAC GROUP UK

Project: THE BARNS, HALEWOOD

Title: SOFT LANDSCAPE PLAN 3/3

Issue: PLANNING

Drawn:	Checked:	Approved:
TH	SW	SA
Project: UG2864	**Scale @ A1:** 1:500	**Date:** 20/01/25
Dwg No: UG_2864_LAN_SL_DRW_005		**Revision:** P04