



**Dowls Construction Ltd
9 Sandy lane
Skelmersdale
WN8 8LA**

**Remediation Strategy Document
For
Removal of contaminated land**

**Woodend
Netherley Road
Tarbock Green
Knowsley
L35**

Prepared by:
J Taylor CFIOSH/MRSH.IMAPS/MIFSM
Health & safety Management & Training Ltd
61 Seacroft Crescent
Southport
PR9 9FR
Tel: 07802978579

Intoduction

Following a ground investigation report undertaken by Peak Associates Environmental consultants Ltd identified a section of the plot to have hydrocarbons contained within the sample
The area is located towards the front of the plot and is approximately 3x3 mtrs sq

Prior to any construction works these will have to be removed by a specialist contaminated waste contractor and treated.

Pictures are enclosed showing the area to be removed and the top surface layer removed ready for sub base to be removed

All works will overseen by our SHE advisor Mr J Tatlor CFIOSH/IMAPS

Safe work method for removal

- All works to be overseen by Dowls Construction management team to ensure works undertaken to strict safety and Environmental rules
- Area to be completely barriered off to prevent unauthorised access
- The top surface of tarmac and concrete are to be removed to expose the concrete base and the contaminated land underneath
- This will be undertaken by Dowls Construction trained operatives
- When top layer is removed then concrete base will be removed by J&N Plant who will excavated the concrete sub base and place in a designated area for removal by specialist waste contractor
- When contaminated ground exposed this will be removed by specialist waste contractor to a depth of 600mm and placed directly into wagons for removal to recycling centre for treatment
- Specialist waste contractor to provide waste transfer notes for all loads stating volume of loads, and where taken for treatment to leave a paper trail for future reference
- Prior to leaving site then wheels on wagon wheel washed to prevent spread of contamination

Contractors involved

Dowls Construction
Contact: Andy Hewitt 07761 697840

J&N Plant Hire Ltd
Contact: Jake Wallbank 07395 939914

Southport Demolition & Waste recycling centre
Ricky 07831 592288

J Taylor CFIOSH/MRSH/IMAPS/MIFSM

SHE safety advisor for Dowls Construction Ltd
Contact: Joe Taylor 07802 978579

Pictures depicting excavator removing top layer of concrete to expose concrete sub base and contaminated land beneath, are completely barriered off to prevent unauthorised access during works



