

KEY

For Elevations See Drawing ref: (PA)0071

- Type 1 - Existing Brick Wall with Metal Fence Topping - Retained in situ.**
- Type 2 - Existing Brick Wall - Circa 2000mm. Retained in situ depending on S.E comments.**
- Type 3 - Existing Brick Wall - Circa 1100mm high wall.**
- Type 4 - Masonry Brick Wall & Gate - 1800mm high with brick coping, (timber gates, as indicated).**
- Type 5 - Masonry Brick Wall - 900mm high with brick coping.**
- Type 6 - Garden Wall & Railing - 300mm high wall with brick coping, 600mm metal railings atop, 900mm total height.**
- Type 7 - Metal Railings - 900mm high black metal railings.**
- Type 8 - Welded Wire Mesh Fence - 1800mm high, hedge planted on the inside to screen. Secure metal access gate as included.**
- Type 9 - Garden Wall & Fence - 600mm high wall with 1200mm high fence topping, 1800mm total height.**
- Type 10A - Timber Fence & Gates - 1800mm high.**
- Type 10B - Timber Fence & Gates - 1800mm high, heigh permeability (trellising) subject to crime impact assessment.**
- Type 11 - Timber Knee Rail - Circa 450mm high.**
- Type 12 A - Retaining Wall - 1100mm with metal railings on top.**
- Type 12 B - Retaining Wall - 1800mm high, timber fence topping.**
- Type 12 C - Brick Retaining Wall - (no top)**

- Site Access**
- Garden / Communal Area Access**
- Maintenance Access**

- Site external wall - area to be infilled**
- Site external wall - new opening**




View 1




View 2

Low level retaining wall and railings to form new steps



View 3



View 4

Existing garages to be demolished, walls with boundary function to be replaced like for like.



View 5

Existing masonry boundary wall retained in-situ, subject to engineering review

Existing wall retained as boundary

Existing garages to be demolished, walls with boundary function to be replaced like for like.

This drawing is the property of GWP Architecture. Copyright is reserved by them and the drawing is issued on the condition that it is not copied, reproduced, altered, or disclosed to any third party without the prior written consent of GWP Architecture. All drawings and specifications should be read in conjunction with the project contract. Any plan, any possible conflict should be presented to the planning authority. All work to be carried out in accordance with current Building Regulations. Contractors must verify all dimensions on the job before commencing any work or making this drawing. Written dimensions should be taken. Do not take digital dimensions from this drawing. Any discrepancies to be reported to the Architect.

0 2m 10m 20m
Scale - 1:400 @A1

Rev	Date	Comment	Dr	Ch
P06	24.10.25	Planning Issue	MK	DT
P05	30.09.25	General Update	MK	DT
P04	10.09.24	Update following J.E comments	JR	DT
P03	12.08.24	Update following client review	JR	DT
P02	12.08.24	General update	JR	DT
P01	15.07.24	First Issue	MK	DT



CHARTERED ARCHITECTS
INTERIOR DESIGNERS
SPACE PLANNERS
PROJECT MANAGERS
LANDSCAPE ARCHITECTS

01.01 Tower Works, 2 Globe Road, Leeds LS11 5QG
+44(0)113 268 6044 (M) +44(0)113 268 1899 (F)
architectural@gwp-arch.com | www.gwp-arch.com

GWPA Ref (529)2316

Job Title Livv Housing Gaywood Green

Client Livv Housing Group

Boundary Treatments

Name	(529)2316-GWP-01-00-D-A-(PA)-0070		
Scale	1:400@A1	Revision	P06
Drawn/Checked	MK / DT	First Issue	15.07.24
Drawing Status	S2 - Planning		

BIMbaud - NewBIMServer - BIMbaud Basic for Archicad 26/Livv Gaywood Green - (529)2316-GWP-01-00-D-A-(PA)-0070