Planting Schedule

MIXED SCRUB

Qty	Latin Name	Common Name	Height	Form	Rate/Plants m²	%
39	Corylus avellana	Hazel, Cobnut	60-80cm	Whip	3	25
39	Crataegus monogyna	Common hawthorn	60-80cm	Whip	3	25
16	Ilex aquifolium	Holly	60-80cm	Whip	3	10
23	Prunus spinosa	Blackthorn	60-80cm	Whip	3	15
8	Rhamnus cathartica	Common buckthorn	60-80cm	Whip	3	5
31	Rosa canina	Dog rose	60-80cm	Whip	3	20
156						

AMENITY PLANTING

Qty	Latin Name	Common Name	Height	Container Size	Rate/Plants m²	
54	Achillea 'Coronation Gold'	Yarrow 'Coronation Gold'	20-30cm	3L	9	
17	Calamagrostis x acutiflora 'Karl Foerster	Feather Reed Grass	40-60cm	3L	5	
306	Carex oshimensis 'Evergold'	Oshima kan suge	20-30cm	2L	9	
81	Digitalis grandiflora	Foxglove	20-30cm	2L	9	
14	Dryopteris erythrosora	Japanese shield fern	20-30cm	5L	9	
17	Erigeron 'Dunkelste Aller'	Fleabane	20-30cm	1.5-2L	5	
54	Eryngium planum	Flat Sea Holly	20-30cm	1L	9	
69	Euonymus japonicus 'Green Spire'	Spindle tree 'Green Spire'	40-60cm	5L	3	
6	Festuca glauca	Blue grass	20-30cm	1.5-2L	3	
75	Hebe x franciscana 'Blue Gem'	Hebe 'Blue Gem'	40-60cm	5-7.5L	3	
90	Helleborus x sahinii 'Winterbells'	Hellebore	20-30cm	1.5-2L	7	
22	Hylotelephium 'Matrona'	Sedum 'Matrona'	20-30cm	1.5-2L	5	
22	Nepeta racemosa 'Walker's Low'	Catmint 'Walker's Low'	20-30cm	2L	5	
17	Origanum 'Rosenkuppel'	Oregano 'Rosenkuppel'	20-30cm	1L	5	
7	Perovskia atriplicifolia 'Blue Spire'	Salvia 'Blue Spire'	30-40cm	3L	3	
28	Phlomis russeliana	Jerusalem sage	20-30cm	0.5L	3	
4	Pinus mugo	Mountain pine	30-40cm	10-15L	3	
14	Pittosporum tenuifolium ' Golf Ball'	New Zealand Pittosporum	40-60cm	5L	9	
107	Rosmarinus officinalis	Rosmary	40-60cm	5L	3	
5	Rosmarinus officinalis	Rosmary	30-40cm	3L	3	
6	Salvia nemorosa 'Caradonna'	Balkan clary	20-30cm	1.5-2L	3	
5	Sanguisorba officinalis 'Arnhem'	Great Burnet	40-60cm	2L	5	
61	Santolina chamaecyparissus 'Nana'	Dwarf lavender cotton	20-30cm	2-3L	9	
12	Sesleria autumnalis	Autumn moor-grass	20-30cm	2-3L	3	
6	Stachys byzantina	Lamb's ear	10-20cm	1.5-2L	3	
51	Viburnum davidii	David's viburnum	20-30cm	3L	3	
9	Vinca minor	Lesser periwinkle	30-40cm	3L	9	
1167						

INDIVIDUAL TREES

Qty	Latin Name	Common Name	Height	Form	Root Condition	Clear Stem	Girth
5	Acer campestre 'William Cadwell'	Filed maple 'William Cadwell'	350-400cm	Heavy Standard	RB/C	Min. 200cm	12-14cm
1	Amelanchier 'Ballerina'	Amelanchier	250-300cm	Standard	RB/C	150-175cm	8-10cm
4	Betula ermanii	Ermani Birch	350-400cm	Heavy Standard	RB/C	Min 200cm	12-14cm
2	Betula pubescens	Dowy Birch, White Birch	350-400cm	Heavy Standard	RB/C	Min 200cm	12-14cm
5	Carpinus betulus 'Fastigata Frans Fontaine'	Hornbeam	400-450cm	Heavy Standard	RB	Min 200cm	12-14cm
2	Cornus florida	Flowering dogwood	40-60cm	Branched	C		
1	Crataegus monogyna 'Stricta'	Hawthorn 'Stricta'	350-400cm	Selected Standard	RB	Min 200cm	12-14cm
3	Prunus avium 'Plena'	Double gean	350-400cm	Heavy Standard	RB	Min 200cm	12-14cm
1	Prunus padus	Bird cherry	350-400cm	Heavy Standard	RB	Min 200cm	12-14cm
3	Sorbus aria	Whitebeam	350-400cm	Heavy Standard	RB	Min 200cm	12-14cm
1	Sorbus aucuparia 'Autumn Spire'	Rowan 'Autumn Spire'	400-450cm	Heavy Standard	RB	Min 200cm	14-16cm
28							

MIXED NATIVE HEDGEROWS (planted double staggered, 5 plants lin/m)

Qty	Latin Name	Common Name	Height	Form	Root Condition	%	
81	Acer campestre	Field maple	80-100cm	Whip	B	10	
81	Cornus sanguinea	Common dogwood	60-80cm	Whip	B	10	
120	Corylus avellana	Hazel, Cobnut	60-80cm	Whip	B	15	
161	Crataegus monogyna	Common hawthorn	60-80cm	Whip	B	20	
81	Euonymus europaeus	Spindle	60-80cm	Whip	B	10	
40	Ilex aquifolium	Holly	60-80cm	Whip	B	5	
120	Rosa canina	Dog rose	60-80cm	Whip	B	15	
804							

SINGLE SPECIES HEDGEROWS (planted in a single row, 5 plants lin/m)

Qty	Latin Name	Common Name	Height	Form	Root Condition		
281	Carpinus betulus	Hornbeam	60-80cm	Whip	B		



0002



Key Plan NTS @ A1 0003

This drawing is the property of FPCR Environment and Design Ltd and is issued on the condition it is not reproduced, retained or disclosed to any unauthorised person, either wholly or in part without written consent of FPCR Environment and Design Ltd.

N

0 10 20 30m

- Site Boundary
- Existing Vegetation
- Existing Trees: (Extents of existing trees and vegetation within the site. Refer to Arb Consultants Tree Retention Plan)
- Existing Watercourse: Longwood Mill Brook
- Proposed Mixed Native Scrub
- Indicative Proposed Trees
- Proposed Hedges
- Proposed Amenity Grassland: A22 Low Maintenance Seed Mix by Germinal Sowing Rate: 50mg/m2
- Proposed Wildflower Planting Mix 1: WFG21 Everyday Meadow by Germinal Sowing Rate: 15g/2
- Proposed Wildflower Planting Mix 2: Naturescape N11 Dry Soils Meadow Mixture
- Proposed Wildflower Planting Mix 3: Naturescape N6 Clay Soils Meadow Mixture
- Proposed Reinforced Grass: Emergency Vehicle Access Route to be specified by KMA Architects
- Proposed Amenity Planting
- Proposed Paving to Amenity Areas: Marshalls Charnwood Paving, 600 x 600 x 50 mm, Buff, Textured concrete flag, rounded edges
- Proposed Cycle Stands: Broxap Sheffield Cycle Stands, Root Fixed, Galvanised Steel, Height: 800mm, Width: 715mm, Spacing: 1000mm between stands
- Proposed Benches: 4x Broxap Rochester Steel Frame Timber Bench (2000Lmm x 600Wmm), 2x Broxap Willenhall Seat (1800Lmm x 600Wmm)
- Proposed Picnic Benches: 5x Broxap Springfield Picnic Bench (Treated Softwood), 1x Broxap Wheelchair Accessible Land Picnic Bench (Treated Softwood)
- Proposed Shelters: 2x Broxap Litchard Timber Shelter Walkway (Design B with additional Rear Timber Panels and Sedum Roof)
- Proposed General Waste Bin: x3 Langley Litter Bin LLC108: (Timber Clad with Galvanised and Powder Coated Steel Frame)
- Proposed Knee Rail: Height 0.9m
- Security Fencing: to Architects details and specification
- Root Barrier: To be GreenTech Root Barrier 325 or similar approved

Notes:
Existing vegetation to be retained and protected where possible. Whips to be planted in informal groups of 3, 5 or 7, randomly arranged, and protected with shrub shelters (Tubex or similar).

All standard and extra-heavy standard trees to be double staked.

600mm deep root barriers to be installed where trees are located within 3m of footways, buildings, or hard surfaces.

Trees within hard landscape or adjacent to parking areas to be provided with root cells or equivalent to achieve adequate rooting volume.

Trees close to foundation, buildings may require deeper foundation design in accordance with NHBC guidance.

Amenity shrub and perennial planting to be arranged in single-species groups of 3, 5 or 7, randomly arranged to avoid patterning.

Planting within visibility splays to comprise low, slow-growing species only and maintained to a maximum height of 600mm.

No trees or deep-rooting shrubs to be planted within or over drainage, sewer, or service easements without approval. All planting in these areas to be reviewed by the drainage engineer.

All shrub and perennial beds to be mulched with 75mm depth of bark mulch, kept clear of stems and crowns.

All planting to be maintained in accordance with the approved landscape and SuDS maintenance strategy.

rev	date	description	drn / chk
P03	19/12/2025	Removal of tree in SW corner	MW DH

client
JLL Planning UK

project
Linden Hill, Huyton

title
Detailed POS Plan

scale
1:500 @ A1

number
13706-FPCR-XX-XX-DR-L-0002

status
S3

rev
P03

FPCR | environment & design

t: 01509 672772 e: mail@fpcr.co.uk w: www.fpcr.co.uk