IROS*ARB* Appendix 1 Tree Schedule

Project: 33 Huyton Church Road

Review Period: 2 Years

Date: 14/10/2022

ID No	Common Name	Species	BS5837 Category	Age Assessment	ULE	DBH	Height	North	East	South	West	1st Branch	RPA	Vigour	Amenity Value	Notes
T1	Field Maple	Acer Campestre	A	M	>40yrs	550	10.3	6.4	5.4	6.1	6.1	2.5SW	6.6	G	H	An excellent tree with no immediate evidence of biotic disorder. Not impacted by development
T2	Lime	Tilia x europaea	B	M	>20 yrs	400	12	7.2	7.1	7.7	5.9	4W	4.8	M	H	An excellent tree with no immediate evidence of biotic disorder aprt from evidence of dieback in crown. Not impacted by development
T3	Ash	Fraxinus excelsior	A1	M	>40yrs	450	14.2	6.5	7.5	7.5	7.2	7E	5.4	G	H	An outstanding tree of excellent vigour and original morphology. No immediate evidence of biotic disorder (including ADB). Not impacted by development
T4	Pear	Pyrus calleryana	B	M	>20yrs	390	10.8	2.5	5.9	5.9	3.5	4E	4.68	M	L	A moderate tree with a number of lesions to stem. Not impacted by development
T5	Cypress	Cupressus sp	B	M	>20yrs	370	11.5	2.5	5.1	5.1	2.5	n/a	4.44	M	L	A large tree not impacted by development
T6	Cypress	Cupressus sp	C	SM	<20 yrs	230	9.5	0	2.2	3.1	2.1	n/a	2.76	P	L	Subdominant and rather poor. Not impacted by development.
T7	Beech	Fagus sylvatica	B	SM	>20yrs	360	11.5	2.1	5.9	4.8	2.2	3E	4.32	M	L	Heavy phototropic lean and somewhat moderate form. Not impacted by the development.
T8	Lime	Tilia x europaea	B	M	>20yrs	640	17.2	6.5	6.5	6.5	6.5	4W	7.68	G	H	A very large and dominant tree but with some dieback in crown. Not impacted by development.
H1	Mixed	n/a	B	M	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	G	M	n/a
H2	Beech	Fagus sylvatica	B	M	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	n/a	G	M	n/a