



GENERAL NOTES

- All planting and seeding to be undertaken during the first planting season following completion of infrastructure.
- Deciduous trees and shrubs: Late October to late March.
- Conifers and evergreens: September/ October or April/ May.
- Container grown plants: At any time if ground and weather conditions are favourable (provide watering and weed control as necessary).
- Existing trees to be retained and protected throughout construction period in accordance with BS 5837 2012 - Trees in Relation to Design, Demolition and Construction - Recommendations.
- Materials and workmanship shall generally be in accordance with the following documents - BS3936 Nursery Stock and BS428. Recommendations for General Landscape Operations. Plant material to be the sizes and dimensions as stated in the schedule and shall be healthy with good fibrous root systems.
- Site Preparation: Break up compacted soil to full depth for planting areas. Remove undesirable material brought to the surface. Apply approved herbicides as per manufacturer's guidelines to all areas to be seeded or planted and allow suitable time to elapse to ensure all weeds are dead before cultivation. Leave regular and even.
- Setting out of planted areas to be approved on site by Contract Administrator (CA). All tree and shrubs to be planted in top soil @ 450mm depth. Amenity Grass Areas will be sown in top soil @ 150mm depth.
- Woodland and shrub mix amended in accordance with UU Standard Conditions.

PLANTS/TREES - GENERAL

- Condition: Materially undamaged, sturdy, healthy and vigorous.
- Appearance: Of good shape and without elongated shoots.
- Hardiness: Grown in a suitable environment and hardened off.
- Health: Free from pests, diseases, discolouration and weeds.
- Budded or grafted plants: Bottom worked.
- Root System and Condition: Balanced with branch system.
- Standard: The relevant parts of BS 3936.
- Species: True to Name.
- Origin/Provenance: British provenance as per the National Plant Specification.
- Names, Forms, Dimensions, Provenance and other Criteria: To BS 3936-1 Trees and Shrubs.
- Where proposed trees are located adjacent to roads/pathways root protection barriers to be provided on footpath side of tree pit. Where landscape works encroach on root protection areas non-dig / hand dig methods to be used in accordance with the Arboricultural Method Statement.

PLANTING OF TREES AND SHRUBS: -

- Individual trees to be double staked and tied above ground.
- All trees to be back filled with top soil and suitable organic material (to be specified). All trees to be protected by tree guards. Trees located within the highway edge or other public pedestrian locations within the site will need to be adequately protected (selected system to be approved). Trees planted in bare ground to have 1m radius circle of woodchip or crushed bark mulch to a depth of 100mm.



SHRUB PROTECTION:

- Manufacturer: Contractor's choice, to LA approval.
- Material: UV stabilised Polypropylene Shrub Shelter
- Size: 600mm high 63mm diameter.
- Support: Stout bamboo cane or softwood alternative.

PLANTING MAINTENANCE GENERALLY- REFER TO LANDSCAPE MANAGEMENT PLAN

NOTES

This drawing is the property of FPCR Environment and Design Ltd and is issued on the condition it is not reproduced, retained or disclosed to any unauthorised person, either wholly or in part without written consent of FPCR Environment and Design Ltd.



KEY

- Site Boundary
- Existing vegetation to be removed
- Existing vegetation to be retained
- Existing tree to be retained
- Root protection area
- Proposed trees
- Woodland mix (planted at 1.5m centres)
- Native shrub mix (planted at 1m centres)

P02	21/02/2023	Woodland and shrub mix amended	PIM	CEH
P01	15.12.2022	FIRST ISSUE	PM	CEH
rev	date	description	dm	chk

masterplanning

environmental assessment

landscape design

urban design

ecology

architecture

arboriculture

FPCR Environment and Design Ltd

Lockington Hall

Lockington

Derby

DE74 2RH

t: 01509 672772

e: mail@fpcr.co.uk

w: www.fpcr.co.uk

client
Knowsley Redevelopments Ltd

project
Penrhyn Road, Knowsley Business Park,
Merseyside

drawing title
S106 Detailed Softworks Plan

scale
1:500 @ A1

dm
PJM

chk
CEH

date created
15 December 2022

project number
10585

status
S3

issue
P01

document number
10585-FPCR-XX-XX-DR-L-0003

Project Code: L:\10500\10585\LANDS\Drawings\10585 - Planting Plan - 106 Agreement Easement Overlay P02.vwx

Planting Schedule								
NATIVE WOODLAND MIX								
Qty	Latin Name	Common Name	Height	Form	Root Condition	Rate/m2	Percentage	Girth
6	Acer campestre	Field maple	60-80cm	Whip	BR	0.25	20	
4	Corylus avellana	Hazel, Cobnut	60-80cm	Whip	BR	0.25	15	
7	Crataegus monogyna	Common hawthorn	60-80cm	Whip	BR	0.25	25	
3	Ilex aquifolium	Holly	60-80cm	Whip	BR	0.25	10	
4	Prunus spinosa	Blackthorn	60-80cm	Whip	BR	0.25	15	
1	Prunus padus	Bird cherry	175-200cm	Feathered	RB	0.25	5	
1	Prunus avium	Wild cherry	175-200cm	Feathered	RB	0.25	5	
1	Acer campestre	Field maple	175-200cm	Feathered	RB	0.25	5	
2	Acer campestre	Field Maple	350-400cm	Heavy Standard	RB	0	0	12-14cm
2	Prunus padus	Bird cherry	350-400cm	Heavy Standard	RB	0	0	12-14cm
1	Prunus avium	Gean, Wild cherry	350-400cm	Heavy Standard	RB	0	0	12-14cm
NATIVE SHRUB MIX								
Qty	Latin Name	Common Name	Height	Form	Root Condition	Container	Percentage	
6	Acer campestre	Field maple	60-80cm	Whip	BR		20	
8	Corylus avellana	Hazel, Cobnut	60-80cm	Whip	BR		30	
8	Crataegus monogyna	Common hawthorn	60-80cm	Whip	BR		30	
1	Ilex aquifolium	Holly	40-60cm	Whip	C	2L	5	
1	Prunus spinosa	Blackthorn	60-80cm	Whip	BR		5	